

Project: 851 3rd St

HRA of St. Paul Neighborhood Stabilization Program

Addendum#1

This Addendum forms a part of the Architectural Specification and Drawings. It modifies the "Bid Set" of documents: Specification and Drawings dated 7/26/12. The additions, revisions, corrections, and clarifications contained herein shall be made to the drawings and specifications for the project and shall be included in the scope of work and in the revisions to the bids to be submitted. References made below to drawings and specifications shall be used as a general guide only. Bidders and Contractors shall determine for themselves all of the work affected by Addendum items and acknowledge receipt of the Addendum in submitted bids.

Changes to Specifications:

07 6200 - Sheet Metal Flashing and Trim

Delete:

A. Take out LP smart board for window and door wraps. Soffit, fascia and trim will be White Sheet Metal.

07 4646 - Fiber Cement Siding

Delete:

B. Remove Line item letter D in **fiber cement** board section. White Sheet Metal flashing and trim will be installed only

09 3000 - Tiling

Add:

C. Add 2nd floor bathroom tiling. Upstairs Master Bathroom tub surround is getting a 6*3 white subway tile. Refer to durarock installation section where states to install durarock in master bathroom for tile.